

KITCHEN REMODEL — ESTIMATE

Contractor: _____ **License No.** _____
Address: _____ **Phone:** _____
Prepared for: _____ **Macone** — _____ **Prospect Street,**
_____, NY _____ **Date:** _____, 2026 · **Valid for 30**
days

All prices below are **LABOR ONLY**. The homeowner purchases all cabinets and materials directly from The Home Depot. Choose one option; a full contract will be written for the option selected.

OPTION A — Cabinet Replacement Only

Replace the existing kitchen cabinets on two walls. Walls stay in place. No structural, electrical, or plumbing work.

Cabinet run = 14'2" wall + 12'7" wall = 26'9", **less** the refrigerator (36") and stove (30") openings on the 14' wall = **~21 linear feet** of cabinets.

Work

Remove existing cabinets on both walls (~21 linear ft) + haul away	included
Remove and replace the sheetrock (drywall) behind the cabinets on both walls; tape, mud & finish to paint-ready	included
Install new Owner-supplied cabinets — uppers & lowers, set level, plumb, secured, doors/drawers adjusted	included
Pull out / reset & reconnect refrigerator and stove; leave correct openings	included
OPTION A TOTAL LABOR	\$8,000

Payment: 50% down at signing (\$4,000), 50% at completion (\$4,000). *Homeowner materials (cabinets, est.):* ~\$2,100 – \$6,300 at Home Depot. *If gas stove:* add a licensed gas-fitter reconnect, ~\$150–\$400 (homeowner-paid pass-through).

OPTION C — Cabinet Replacement + Island

Everything in Option A (cabinets on both walls, new sheetrock, appliance handling), **plus** a new center island — walls stay in place, no structural work.

Work

All Option A work (remove old cabinets ~21 LF, included
new sheetrock both walls, install new cabinets,
reset fridge & stove)

Assemble, set, level & anchor a new included

Owner-supplied island cabinet base

OPTION C TOTAL LABOR \$10,000

Payment: 50% down at signing (\$5,000), 50% at completion (\$5,000). *Homeowner materials (cabinets + island, est.):* ~\$2,600 – \$7,500 at Home Depot. *If gas stove:* add a licensed gas-fitter reconnect, ~\$150–\$400 (homeowner-paid pass-through). *Island electrical (outlets in island, if wanted):* add by written Change Order — not in this price.

OPTION B — Full Open-Concept Remodel

Open the kitchen by removing two load-bearing walls, add a center island, and install new cabinets throughout.

Work

Remove two (2) load-bearing walls; temporary included
shoring; install engineered beam & posts per NY
licensed engineer's stamped design

Re-wire outlets/switches/wiring in the removed included
walls to code

Close, tape, mud & finish ceiling and walls to included
paint-ready

Patch and infill flooring where walls were included
removed

Remove existing cabinets + haul away included

Install new Owner-supplied cabinets throughout, included
plus center island (level, anchor, electrical for
island outlets)

OPTION B TOTAL LABOR \$24,000

Payment: three milestones — down / structural complete / final. *Owner-paid pass-through (not in labor price):* structural engineer's stamped beam design **\$800 – \$2,000**; building permit & inspection **\$500 – \$1,500**. *Homeowner materials (cabinets, beam, electrical, drywall, flooring, est.):* homeowner-supplied at Home Depot.

Summary

	Option A — Cabinets Only	Option C — Cabinets + Island	Option B — Full Remodel
Wall removal	No	No	Yes (2 walls)
Island	No	Yes	Yes
New cabinets	Yes (2 walls)	Yes (2 walls)	Yes (throughout)
New sheetrock behind cabinets	Yes (both walls)	Yes (both walls)	Yes
Electrical / flooring	No	No	Yes
Labor	\$8,000	\$10,000	\$24,000

This is an estimate, not a contract. A full home-improvement contract will be prepared for the option chosen. Materials are Owner-supplied. Prices exclude countertops, backsplash, appliances, plumbing relocation, painting, and hazardous-material abatement unless added by written Change Order. Not legal advice — have a local attorney review the final contract.